New Home Sales Estimate

Clarendon Homes

Document No. 2 | Document created date 21/03/2026

Job Number | Lead Number L161138 | Sales Consultant Jake Anderson

Client's File Name

Contact 1

Title | **Surname** Jones | **Given Name** Simon

Phone (Mobile) +61401301726 | **Phone** (Home) | **Email** essgjay@mac.com

Primary Address

Contact 2

Title | **Surname** | **Given Name**

Phone (Mobile) | **Phone** (Home) | **Email**

House Type **Antigua 270** | Facade **Portofino - Face Brick**

Site Address **Lot 3 32 Grosvenor Street BALMORAL QLD 4171**

Base House Pricing

1 - 1	Antigua 270 Traditional Aspire. (Face Brick-Excludes Applied Finishes)	$441,400

Contact 1 Name: **Simon Jones** | Contact 1 Signature: _____

Contact 2 Name: | Contact 2 Signature: _____

Facades

2 - 7	Provide Antigua 270 Portofino Facade in lieu of Traditional facade	$31,900

Includes:
- Face brick finish from builder's standard range of bricks with builders standard mortar & mortar joint.
- Incudes lightweight wall with CSR Cemintel headland cladding to section of the front facade.
- Incudes Balcony with powder coated aluminium balustrade.
- Incudes timber framed post with FC sheet lining and decorative timber trims in a painted finish.
- Includes front gable with lightweight cladding.
- Includes window changes.

Floorplan Options

3 - 7	Provide Antigua 270 1200mm front Entry door Option • Includes a 2040mm x 1200 Pmad104 hinged entry door.	$1,850
3 - 11	Provide Antigua 270 Rumpus To Front w/ Flipped Bed 1 & Balcony Option	$22,800

Contact 1 Name: **Simon Jones** Contact 1 Signature: _____

Contact 2 Name: Contact 2 Signature: _____

Promotions

5 - 3 ASPIRE - YOUR STYLE PROMOTION $7,990
Effective 1st December 2025

TILING AND CARPET
· 450mm x 450mm pressed edge vitrified ceramic tiles to your main internal floor areas with a great range of colours and sizes to choose from in a matt finish. Ask a sales consultant for the floor covering layout for your chosen home design.
· Premium quality Australian made loop pile carpet for a luxurious feel under foot and maximum longevity and wear. With a selection of stunning colours available, you are sure to find an option to suit your home's style and décor. Includes quality 7mm underlay throughout. Ask a sales consultant for the floor covering layout for your chosen home design.

Further conditions apply. For full terms and conditions, speak to a Clarendon Homes New Home Consultant.

5 - 4 ASPIRE - YOUR STYLE PROMOTION $2,990
Effective 1st December 2025

2590MM HIGH CEILINGS
o For your single storey home, you'll receive 2590mm high ceilings throughout, including painted FC sheet infills to above your windows externally; or
o For your double storey home, you'll receive 2590mm high ceilings to your lower floor, perfectly complemented by your standard 2440mm high ceilings to your upper floor.

Further conditions apply. For full terms and conditions, speak to a Clarendon Homes New Home Consultant.

5 - 6 ASPIRE - YOUR STYLE PROMOTION $390
Effective 1st December 2025

DESIGNER BATHROOMS
· Full height tiling to the vanity wall in your master bedroom ensuite.
· A choice of Phoenix Arlo, Teva or Pina chrome wall mounted basin mixer sets.
· A choice of Fienza Reba or Sarah semi inset designer basins with no tap hole, to suit wall mounted vanity tapware.

Further conditions apply. For full terms and conditions, speak to a Clarendon Homes New Home Consultant.

5 - 8 ASPIRE - YOUR STYLE PROMOTION $790
Effective 1st December 2025

REFINED LAUNDRY
· Up to 900mm wide two door melamine laundry cabinet with 45 litre stainless steel sink and choice of designer handles.

Further conditions apply. For full terms and conditions, speak to a Clarendon Homes New Home Consultant.

Contact 1 Name: **Simon Jones** Contact 1 Signature: _____

Contact 2 Name: Contact 2 Signature: _____

Price Review

6 - 2 9 MONTH PRICE PROMISE Promotion

I/We acknowledge the Clarendon Homes' "9 Month Price Promise" has been explained to me/us, and I/we understand that this price lock takes effect from the date of initial deposit.

I/We understand and acknowledge that in return for paying my/our initial deposit, Clarendon Homes will hold the base price of the house, façade price, standard inclusions and promotional offer (if applicable), as set out in the Sales Estimate for 9 months in lieu of the standard 7 months, provided that I/we comply with the timeframes/milestones set out by Clarendon Homes as below:

· I/We must sign our Sales Estimate within 7 days of payment of initial deposit
· I/We must sign our Preliminary Building Agreement (and pay any/all additional deposit amounts required at this stage) within 7 days of presentation of the Preliminary Building Agreement
· I/We must sign our Building Agreement and HIA contract (and pay the balance of 5% deposit) within 7 days of presentation of the Building Agreement and HIA contract
· I/We provide evidence of ownership of title to our land and all “supporting documentation” (see note below) by no later than 6 months from deposit date.
· I/We must sign our selection documents including tile, electrical, Lifestyle studio selections, floor covering, air conditioning, data, robe fit out and security/window screens within 7 working days of the relative selection appointment.
· I/We achieve the Price Review Date (also referred to in the HIA contract as “Anticipated Start Date (ASD)” on or before 9 months from the date of initial deposit.

“Supporting documentation” includes:
o Satisfactory evidence of our title to the land
o Copy of the registered survey plan
o Copy of as-constructed drawings
o Full access to the land to conduct soil testing and contour surveys
o Copy of compaction report if applicable

Price Review Date requirements
1. Land registered and settled
2. All permits and approvals received
3. Finance approval received and funds ready to be released
4. Deposit paid
5. Demolition complete 3 weeks prior to the ASD
6. Tree removed and site clean
7. All specification, selection and construction documents signed

I/We understand and acknowledge that if we do not meet any of the above timeframes:

· If contract has been signed, Clarendon Homes will have the right to terminate and reprice.
· If contract is not yet signed, all items in the job will be reviewed and repriced automatically.

Contact 1 Name: **Simon Jones** Contact 1 Signature: _____

Contact 2 Name: Contact 2 Signature: _____

Site Costs

7 - 1	This Building Agreement is subject to a contour survey becoming available. • Note: Client acknowledges and accepts any additional costs associated with Earthworks, Services, and any unforseen site items once Contour Survey is received.	Note
7 - 2	This Preliminary Building Agreement is subject to a soil report becoming available. • Note: Client acknowledges and accepts any additional costs associated with Slab, Piering and any unforseen slab items once Soil Report is received. • Any additional costs will be adjusted by a variation in accordance with Clause 20 of the Contract.	Note
7 - 4	Earthworks: Provide an equal cut and fill to up to 1000mm fall across the block to achieve a level building platform. Note: Allows for up to 350m2 building PAD only.	$1,170
7 - 8	Provide for removal of spoil from KDR Site from drainage trenches due to Contaminated soils on Site.	$3,735
7 - 9	Client to remove any spoil/rubbish stockpiles from site prior to site start. If this is not done additional charges for Clarendon Homes to remove will be passed onto the client by means of a Post Contract Variation.	Note
7 - 10	Client to Clear/Slash existing vegetation from building site prior to site start. If this is not done additional charges for Clarendon Homes to remove will be passed onto the client by means of a Post Contract Variation.	Note
7 - 11	Note: Client is to provide entire site free of fire ants prior to site start. Should fire ants be detected prior to site start client is responsible to provide authorised inspection and eradiction control. Should fire ants be detected after site start any costs involved to provide inspection and removal shall be bourne by the client.	Note

Contact 1 Name: **Simon Jones** Contact 1 Signature: _____

Contact 2 Name: Contact 2 Signature: _____

Building Platform

8 - 5	Provide Additional Costs for access and handling for tradesmen and suppliers due to the nature of the block. Includes but not limited to: - Additional site cleans - Hand cleans - Manual handling for bricklayer - Tight site charges for Carpenter and Concreter - Cranage - Safety scaffolding to suit narrow block - Steep blocks that prevent storage or machine access - Nature strip hire due to lack or storage area - Power lines preventing cranage access - Limited access to the sides of the home preventing machine access - Split Deliveries due to limited access - Large Trees that create limited access	$5,000
8 - 6	Provide for the supply of Safety mesh to scaffolding sections of the roof edge to comply with WHS requirements.	$590
8 - 7	Provide for overhead barrier tape/bunting to existing power line.	$1,520
8 - 10	Provide for a zero lot to the Garage including - Roof edge protection for walls above 3.0m high. - Extend the slab rebate to suit zero lot. - Provide for a max 400mm high drop edge beam to the side of the Garage. - Provide for Non-Combustible downpipes as required. - Rockwool insulation between rafters on boundary wall. - Excludes Piering and additoinal scaffold requirements (to be charged for separately) -Note: Client is to arrange permission from the owner of neighbouring block for access for the builder. If this is not granted additional costs to the client will be incurred. -Note: Client to remove existing fence adjacent to Garage and reinstate after handover if applicable.	$2,850
8 - 11	Provide additional scaffold/ edge protection fee due to Zero boundary. NOTE: Required when Zero boundary wall is higher than 3.0m, has a parapet on boundary wall or retaining lower than platform on boundary)	$1,500
8 - 13	Trees to the front of the property are to be removed prior to site start. Client is to engage council and get approval to do this. • All site costs are subject to a satisfactory Builders site inspection prior to commencement of construction to ensure tree are removed. • If approval is not granted to remove the trees, No responsibility will be taken by the builder for damage or death of the tree. The client takes full responsibility for the trees to the front and any associated council matters. Trees will need to be trimmed back to suit access to build the house and will be at the builders discretion as to how much will need to be trimmed.	Note
8 - 14	Provide additional site investigations for KDRB including; - Surcharge for contour and detail survey with existing house. - One (1) additional contour survey after house has been removed. - One (1) additional Soil Test after house has been removed.	$2,943

Contact 1 Name: **Simon Jones** Contact 1 Signature: _____

Contact 2 Name: Contact 2 Signature: _____

8 - 15	Once house has been removed, the builder will conduct a second Survey and Soil test to determine if the removal of house has changed any site conditions. This Building agreement has been priced on the site survey and soil report available at the time prior to house removal. Costs associated with new information resulting from the second soil and survey report will be borne by client. • Note: Client acknowledges and accepts any additional costs associated with Earthworks, Services, Slab, Piering and any unforseen site items once second Contour Survey and second Soil Report are received.	Note
8 - 17	Provide 63amp three phase overhead power connection to a permanent timber property pole inside boundary, then underground electrical connection from property pole to meter box located on left/right side of Garage/Living/Study/Lounge. • Please note pricing has been based on the provision that the permanent property power pole can be installed prior to commencement of construction to reduce time delays for Energex power connection. • Any time delays for power connection which incur additional costs for generator hire to the Builder will be deducted from the Provisional Allowance in the Contract. • All weather access for a flat stable path 6m wide from kerb to proposed pole location, clear of any trees or obstruction, is required prior to install. If this is not provided, a return visit will be required and fees will be charged by way of variation. • Note: Three Phase power has not been found on site. Client to arrange with Energex, prior to a site start, to have three phase availability installed to the front boundary for future connection by Clarendon homes. ********** • NOTE: If an EV charger is included, allowances should be made for 80amp upgrade.	$4,090

Services

9 - 1	Stormwater drainage system has only been designed to cater for works by Clarendon Homes within proposed building platform as shown on site plan and does not consider any future works by owner after handover. Clarendon Homes does not take any responsibility for possible failure of system due to future works by owner.	Note
9 - 3	Provide field gully traps 5No as positioned on site plan.	$700
9 - 5	Provide costs for cut out and removal of concrete and installation of a Kerb adapter as required for the run of stormwater to the street.	$225
9 - 22	Clarendon Home will use their nominated Energy Connections Retailer to facilitate the connection of power in the customers' name for the duration of the build. This account is non-binding and the Customer can re select their preferred electrical retailer after construction is complete. It is the customers' responsibility to pay for all electricity consumed by the builder during the construction It is also the Customers' responsibility to pay for all mandatory metering/account establishment fees associated with power connection.	Note

Contact 1 Name: **Simon Jones** Contact 1 Signature: _____

Contact 2 Name: Contact 2 Signature: _____

Structural Engineers Requirements

11 - 5	Provide "H2" Slab Classification in lieu of "M" class slab as per Engineers Report. Not included- - Flexible joint for Sewer connection due to "H" Class slab. - Additional sand to backfill services trenches as required for Highly reactive "H class" soils or Rock Soils or Clay Soils.	$6,190
11 - 8	Provide Expansion Joints to Downpipes to suit H1, H2, E & P class sites.	$690
11 - 9	Provide Vertical Risers to drainage points to suit "P" class site.	$1,920
11 - 10	• Provide flexible joint for Sewer connection due to "H" Class slab. • Provide additional sand to backfill services trenches as required for for Highly reactive soils	$1,830.00
11 - 11	Provide increased tie-down, bracing and structural adequacy, to suit Terrain Category N3 (W41) as per Engineers Report.	$5,137

Provisional Allowances

13 - 2	KDRB: Provide for a Provisional allowance for screw piering to the slab as per the engineer due to; • Existing house • Builders fill side of earthworks. • Influence of existing trees. • Existing services. • Proximity to boundary retaining. • Influence of clients future pool. • Poor bearing soils. • Uncontrolled fill.	$15,000
13 - 4	Provide a Provisional Sum for Traffic control requirements to allow access to site in accordance with Main Roads regulations. "Clarendon Bronze Level"	$6,000
13 - 5	Provide for a Provisional allowance for generator hire to provide power to site prior to electrical meter being connected.	$1,000

Contact 1 Name: **Simon Jones** Contact 1 Signature: _____

Contact 2 Name: Contact 2 Signature: _____

Client Reminders

15 - 1	It is the clients responsibility to gain all relevant covenant approvals and ensure all covenant requirements are met.	Note
15 - 2	Client to provide retaining walls if necessary to site when requested by Clarendon Homes.	Note
15 - 3	Client to retain and stabilise all other cut & fill batters after Handover.	Note
15 - 4	Client to relocate trees with Local Authority vegetation protective services for driveway access.	Note
15 - 5	NOTE: The Client is to demolish and remove from site existing house and outbuildings, including footings and services above or below ground, paths, drive and fences etc prior to commencement of construction (Any separate council application to demolish the existing house is the clients responsibility, please check with your local council). • Demolition is to be completed a minimum of three weeks prior to the anticipated start date to allow for secondary reports, amended engineering and construction documentation to be completed. • Client to provide Clarendon Homes with Local Council Approval for house removal/demolition. Client to also provide Clarendon Homes Final Inspection Certificate after removal/demolition; • Client also agrees to provide Clarendon Homes a Hygienist Clearance Certificate certifying that there is no residual asbestos left on site after the demolition has been completed. • Clarendon Homes to provide additional site inspection after house removal/demolition to re-evaluate the site costs. Items that may be assessed are pad level, any additional compaction requirements, if any due to disturbance in soils and onsite drainage requirements; • Clients to cap off and identify all services above ground level after existing house removed and prior to the commencement of earthwork, Client acknowledges and accepts any additional costs associated with locating of the services connection points. • Following completion of demolition works, the Client must engage a suitably licensed plumber to inspect and certify the capping of the sewer connection. A Form 1 must be provided prior to site commencement. For the avoidance of doubt, a Form 4 will not be accepted as evidence of compliance for this purpose. All costs associated with obtaining the required certification shall be borne by the Client. Further information regarding these requirements is available on the Contractor's website. • Note: Client acknowledges and accepts any additional costs associated with additional earthworks, importing/exporting fill, any additional compaction requirements, removal of any additional material found on site, drainage issues, services issues and any other unforeseen site items during the site inspection and will included any unforeseen items found during course of construction.	Note
15 - 6	Client to provide Ident survey and have pegs reinstated prior to earthworks by Clarendon Homes.	Note

Contact 1 Name: **Simon Jones** Contact 1 Signature: _____

Contact 2 Name: Contact 2 Signature: _____

15 - 7	These specifications incorporate the QBCC Standards and Tolerances Guide. The client agrees that he/she has had access to review a copy of the Guide. The Guide can be accessed digitally at <https://www.qbcc.qld.gov.au/resources/guide/standards-tolerances-guide> The parties agree to use the QBCC Standards and Tolerances Guide as a point of reference for information on industry accepted workmanship standards and tolerances in deciding whether an alleged defect exists and/or whether the materials used and/or workmanship are in accordance with the plans and specifications. The QBCC Standards and Tolerances Guide will be used in priority to any other guide on standards and tolerances.	Note

Council fees - BCC

16 - 2	Provide Council Fees for New Driveway Crossover as per Brisbane City Council.	$550
16 - 3	Provide Brisbane Council additional fees for FIRST setback relaxation. This contract is subject to Local Authority approval for relaxation being granted. Note: Client to obtain neighbour's written consent.	$1,450

Contact 1 Name: **Simon Jones** Contact 1 Signature: _____

Contact 2 Name: Contact 2 Signature: _____

Energy Efficiency

24 - 1 7 STAR ENERGY EFFICIENCY — Note

With our focus on smarter, more sustainable living, you can enjoy a home that's not only comfortable but also cost-effective for years to come.

The following upgrades to your home have been included to contribute to energy efficiency compliance. .

• Anticon insulation/ sarking
• Whirly birds (x2) and Eave snap vents
• Ceiling fans as required
• R2.0 batts with sisalation to all external walls
• Additional ceiling R3.5 batts
• R3.5 batts to floors above Alfresco/ Porch
• R2.0 batts to the internal Garage wall
• Planibel G 'Low E' clear glazing to all windows and sgd's except wet ares. (Applies to ALL Double Storey homes and acreage Single Storey homes only)

Due to the nature of the NCC 2022 updates, the necessary requirements (and associated costs) to achieve compliance may vary significantly based on your chosen home design, the siting of your home on your block of land and your chosen colours. Clarendon Homes have based the current assessment on a medium colour scheme and the above provisions. For these reasons, Clarendon Homes can only determine the final requirements and costs to achieve compliance once you have completed all design and colour selections. Requirements are subject to final colours and electrical selections.

Any additional upgrades required to achieve energy efficiency compliance will be an additional cost to this contract, bourne by the owner/s.

24 - 2 Provide an Energy Efficiency upgrades allowance. — $3,000

Due to the nature of the NCC 2022 updates, the necessary requirements (and associated costs) to achieve compliance may vary significantly based on your chosen home design, the siting of your home on your block of land and your chosen colours. As a result, modifications to your floorplan or additional inclusion upgrades (or both) to achieve 7 star compliance may be required.

The unused portion of the Energy Efficiency Allowance will be credited once:
• All relevant council, covenant, and certifier approvals have been issued to the builder.
• All final selections have been completed and signed off by the owners.
• A final NatHERS assessment has been completed before construction commencement and confirms compliance.

NOTE: Any additional changes required to achieve a building approval that are not included in the current specification and building agreement will be amended by variation per Clauses 11 and 20 of the Contract, with all associated costs being included in the final price to the owners.

Council notes

29 - 1 Tender subject to the final private certifiers preliminary assessment. (Any additional costs for council requirements or services if any to be Borne by Client.) — Note
• If no allowances have been made for Bushfire, Acoustic or Flood requirements, and become known at time of pre-assesment, any additional costs relating to the above assessment will be an additional cost to this contract, borne by the Client.

Contact 1 Name: **Simon Jones** Contact 1 Signature: _____

Contact 2 Name: Contact 2 Signature: _____

Colours

30 - 1	Provide Allowance for client's budget purposes for when you attend your Colour Studio Appointment with our Colour Consultant who will provide professional advice and attend to your upgrade option requirements.	$8,000
30 - 5	Provide Exposed Aggregate Driveway (50m2) from Builders Standard Range as shown and positioned on Site Plans. -Excludes Sealing of Aggregate. -Driveway to have maximum gradient of 1:6 and positioned to comply with council requirements. -Although every effort is made to ensure aggregates are free from foreign material and inconsistencies, aggregates are a natural product and may contain ironstone which may cause staining.	$11,300

Electrical Upgrades

31 - 1	Provide Allowance for client's budget purposes for when you attend your appointment with our Electrical Consultant who will provide professional advice and attend to your upgrade option requirements. Allows for up to **kw Solar System. Note: Solar system may be required to be selected through Zurcorp electrical consultants to comply with 7 star “whole of Home' energy requirements, due to clients proposed pool being installed during construction. Client to provide details of pool dimension and depths, along with specification of proposed pool pump prior to building agreement.	$8,000
31 - 3	Fully Ducted Air Conditioning Double Storey B Single Phase Provide Rinnai DONSR15B1 / DINLR15B1 air conditioning Day/Night zoned ducted reverse cycle air conditioner to Double Storey including outlets to suit, 2 x Zones, including outlets to suit, 2 x Zones complete with 7" inch 'Zone touch' LCD colour touchscreen zone control, 3 phase wiring only to 3 phase meter box, boxing in of duct droppers and roof truss strengthening - The Day/Night air-conditioning system is based on a standard house type only. If the home has been extended or remodeled, our recommendation is that the Day/Night air-conditioning system be upgraded to suit. - The Day / Night air conditioning is designed on the principals of providing comfort cooling / heating to the Day Zone or alternately the Night Zone . Acoustic protection, if required by council, is the client's responsibility and is not included in this Tender / Home Building Agreement amount. - Requires single phase 32amp circuit.	$14,394

Contact 1 Name: **Simon Jones** Contact 1 Signature: _____

Contact 2 Name: Contact 2 Signature: _____

Structural Changes

34 - 1	VARIATIONS TO THE PRELIMINARY BUILDING AGREEMENT	Note

Once your Preliminary Building Agreement has been issued, we're happy to review any requested changes.

However, if a significant number of changes are requested, a re-tender may be required. This helps ensure your pricing remains accurate and up to date.

A re-tender may be required where:

· more than 15 changes are requested

· Lifestyle Options are changed

· the façade is changed in conjunction with 5 or more changes

Wet area upgrades

37 - 1	Provide approx 350mm (H) x 650mm (W) tiled shower niche to Bed 1 Ensuite shower. -Exact dimensions to be determined on site.	$390
37 - 2	Provide approx 350mm (H) x 650mm (W) tiled shower niche to Bathroom shower. -Exact dimensions to be determined on site.	$390
37 - 3	Provide approx 350mm (H) x 650mm (W) tiled shower niche to Powder shower. -Exact dimensions to be determined on site.	$390

Total Price **$620,064.00**

Note:
Prices shown are estimates only. Additional costs may apply for further alterations or additions to the house design, façade design or inclusions specified. Additionally, further costs may apply as a result of statutory authority requirements, site specific requirements and/or variations arising from further analysis of your block of land to be carried out by or on behalf of Clarendon Homes, subject to your acceptance of this New Home Sales Estimate and payment of an initial deposit to Clarendon Homes QLD.

**For full terms and conditions go to www.clarendon.com.au/qld/terms-and-conditions*

Contact 1 Name: **Simon Jones** Contact 1 Signature: _____

Contact 2 Name: Contact 2 Signature: _____

Aspire Collection: Standard Inclusions

Effective for initial deposits paid from 1st July 2024

FLOOR
- Class "S" concrete slab on level site.

EARTHWORKS
- Up to 500mm of fall over the building platform.

CONNECTIONS
- 63 amp underground 3-phase power, water, stormwater and sewerage connection to 800m2 lot with a maximum 6.0m house setback.

WIND RATING
- Built tough to an N2 wind rating.

INSULATION

Single storey homes
- R2.0 batts and sisalation to all external walls
- R2.0 batts to internal garage/house wall
- R3.5 batts to roof space including alfresco, garage and porch.

Double storey homes
- R2.0 batts and sisalation to all external walls
- R2.0 batts to internal garage/house wall
- R3.5 batts to roof space including alfresco, garage and porch.
- R3.5 batts within the floor trusses of habitable rooms which are located above alfresco and/or porch areas

PORCH
- Plasterboard to ceiling with timber splay mouldings and light point. - design specific.

ALFRESCO
- Plasterboard ceiling with timber splay moulding, light point, double weatherproof power point.
- 1 x 1320mm ceiling fan (white/black) for alfresco spaces <25sqm and 2 x 1320mm ceiling fans (white/ black) for alfresco spaces >25sqm.

ROOFING
- COLORBOND steel roof in Custom Orb profile from Builder's range complete with insulation blanket
- 22.5 degree roof pitch and 450mm eaves - design specific.

CEILING HEIGHTS

Single storey homes
- 2440mm nominal ceiling height throughout unless specified otherwise.

Double storey homes
- 2440mm nominal ceiling height throughout ground and first floors unless specified otherwise.

GARAGE
- 2100mm high automatic sectional overhead door with 2 remote controls.
- Enviro-seal style frame paired with a 40mm thick Endura FLS Composite hinged external door.- design specific.
- Flush panel door to internal access.

TERMITE PROTECTION

Contact 1 Name: **Simon Jones** Contact 1 Signature: _____

Contact 2 Name: Contact 2 Signature: _____

- Service penetration collars and perimeter barrier system to meet the requirements as per Australian Standards 3660.1.

TERMITE RESISTANT FRAMING
- H2-F treatment to softwood members of timber frame, structural joists and trusses.

BRICKS
- Selection of face clay bricks from Builder's Group 1 Range, laid in natural mortar.

CLADDING
Double storey homes
- Brickwork-design specific
- Light weight cladding or fibre cement products to walls above ground floor roof areas - design specific.

Roof ventilation
- 2 x whirly birds and 4 x eave snap vents.

WINDOWS
- Clear low E glass to all windows and sliding glass doors (excluding bathrooms and laundry) - double storeys only.
- Aluminum lockable windows and sliding doors in selected powder coat range of colours.

PANTRY
- 4 equally spaced white melamine shelves.
- Provision for microwave (design specific)

LAUNDRY
- 45 litre stainless steel tub and white coated metal cabinet with concealed by-pass.
- Mixer tap.
- Ceramic tiled splashback to 400mm nominal height over the laundry tub, from Builder's nominated range

BATHROOM, ENSUITE & POWDER ROOM
- 20mm edge stone benchtops with pencil round edge finish.
- Melamine shadowline to benchtop, underbench melamine joinery with ABS edging. Finish/colour from Builder's nominated range (1 x colour only).
- Cabinetry handles from Builder's nominated range.
- Frameless polished edge vanity mirror positioning on tiled skirting above the vanity.
- Vitreous china square inset basin with chrome waste.
- Choice of acrylic baths to bathroom (design specific) from the nominated Builder's range.
- Semi-frameless shower screen with overlap pivot door, clear 6mm safety glass
- Tiled shower base.
- Silver strip drain with tile insert to shower floors.
- Choice of chrome mixers to basins from nominated Builder's range.
- Choice of bath spout and mixers to wall from Builder's nominated range.
- Single function shower rail with choice of shower mixers from Builder's nominated range.
- 600mm or 900mm double towel rail (design specific) to bathroom and ensuite where applicable.
- Hand towel holder to powder room where applicable
- Toilet roll holder to WC, ensuite and powder room where applicable.

HOT WATER SYSTEM
- 280 litre heat pump hot water system for all homes except acreage homes which include 2 x 170 litre heat pumps

Contact 1 Name: **Simon Jones** Contact 1 Signature: _____

Contact 2 Name: Contact 2 Signature: _____

CEILING FANS

- 1 x 1320mm (white/black) four blade ceiling fan to each living room. For double storey homes, 1 x 1320mm (white/black) four blade ceiling fan light to each bedroom as well.

ELECTRICAL

- Meter box located to side of house as nominated by Builder with RCD safety switch and circuit breakers to meter box.
- Double power points throughout with single power points to fridge position, rangehood, microwave, cook top and dishwasher. Hard wiring to smoke detectors & oven.

§ Internal light points: fixed batten point with cowl shades.
§ External light points: to entry & laundry door area.
§ Exhaust fan provided where required for ventilation purposes.
§ Any combination of up to 2 TV points, phone point or data points
§ 1 x double power point and 1 x phone point to garage for NBN
§ Consultation with "Zurcorp Electrical" regarding electrical options.

DOORS

Front entry door

- Painted primed entrance door from Builder's nominated range
- Door furniture from Builder's nominated range.
- Draft seals to comply with thermal energy rating - where applicable.

Laundry door

- Fully glazed aluminium swing door or aluminum sliding door-design specific.

Internal doors

- 2040mm high flush panel doors, paint finish with chrome hinges and latches.
- Door furniture from Builder's nominated range.
- Cushion door stops

Contact 1 Name: **Simon Jones** Contact 1 Signature: _____

Contact 2 Name: Contact 2 Signature: _____

STAIRCASE

- Closed tread carpet grade stairs, painted closed stringers, plasterboard balustrade and painted timber cap.
- Flush panel door to under stair storage (design specific).
- Excludes under stair ceiling, light point and flooring.

ROBES

- Open WIR or vinyl sliding doors with glacier white fronts and bright chrome track and frames.

LINEN CUPBOARD

- 4 white melamine shelves.
- Door furniture from Builder's nominated range.

KITCHEN

- 20mm edge stone benchtops with pencil round edge finish
- 780 wide kitchen island benchtop with 180mm breakfast bar overhang.
- Melamine shadowline to benchtop, underbench melamine joinery with ABS edging. Finish/colour from Builder's nominated range.
- Cabinetry handles from Builder's nominated range
- Choice of designer kitchen sink mixers from nominated Builder's range.
- 1 ¾ bowl stainless steel sink.
- Ceramic tiles to splashback and returns from nominated Builder's range (750mm high).

APPLIANCES

- 600mm electric cooktop from Builder's nominated range.
- 600mm electric under bench oven from Builder's nominated range.
- 600mm canopy rangehood from Builder's nominated range.

CERAMIC TILES

- Wall and bath hob tiles from Builder's nominated range and supplier with tile trim edging (up to 2100mm high in shower recess, up to 1m from floor high over the bath).
- Floor tiles from Builder's nominated range and supplier to all wet areas which includes bathroom, ensuite, powder room, laundry and WC.
- Provision of a single height floor tile as skirting to all wet areas.

PAINTING

Internal

- Skirtings, architraves and doors - gloss enamel.
- Ceilings - flat acrylic two coat paint system in Victorian Builders White.
- Walls - Matt three coat paint system.
- Note: one colour for walls, doors, skirtings, and architraves throughout.

External

- Front entry door - gloss enamel paint
- Other doors and woodwork - low sheen acrylic - one colour throughout.

Contact 1 Name: **Simon Jones** Contact 1 Signature: _____

Contact 2 Name: Contact 2 Signature: _____

TERMS & CONDITIONS

Clarendon Homes' display homes exhibit items that are not part of our standard inclusion specification. These include, but are not limited to: light fittings, down lights, audio systems, home theatre systems, internal feature walls, ducted air conditioning, window furnishings, timber shutters, security system, flyscreens, door closers, feature wall tiles, internal furniture, carpet, floor tiling, intercom systems, external décor items and works (ie: pergolas, landscaping, timber decking, paving, water features), upgrades to feature materials, bricks, render finishes, ceiling heights, roof pitches, cabinetry, shelving, tapware, kitchen appliances, sanitary ware, laminates, doors, door furniture, natural/composite stone, wall colours, wall finishes and laundry cabinetry.

Clarendon Homes reserves the right to choose the specification, materials and supplier where there is a dispute that may arise in relation to the standard inclusion specification. Clarendon Homes reserves the right to change specifications, materials and suppliers without notice provided that the materials or specifications are of a similar finish and standard.

Variations to Clarendon Homes' standard designs may affect the energy efficiency rating of the home. Any additional costs for items requiring upgrades to the energy efficiency rating arising from variations to the standard design will be passed onto the client in all circumstances.

Clarendon Homes' standard inclusion specification is based on the Traditional façade with face brick finish. Upgraded specifications and materials may be included in the price of façade options.

Rock and/or any unforeseen materials or objects found below the surface of the landowner's property will be at the landowner's cost for the excavation and removal from the property if it has an effect on the construction of the home or building area.

Further condition apply. Please refer to a Clarendon Homes consultant for more information.

Contact 1 Name: **Simon Jones** Contact 1 Signature: _____

Contact 2 Name: Contact 2 Signature: _____